

**11TH FLOOR FRAMING PLAN**

SCALE 1 : 100

1. TOP OF SLAB IS AT ELEVATION AS SHOWN ON ARCH. DRAWINGS EXCEPT AS CROSSED AND NOTED ON PLAN.
2. CONCRETE STRENGTH AT 28 DAYS SHALL BE:
  - FOR WALLS AND COLUMNS ..... SEE SCHEDULE
  - FOR INTERIOR SLABS ..... 25 MPa
  - FOR BEAMS ..... 35 MPa
 CONCRETE EXPOSED TO ELEMENTS SHALL BE 35 MPa WITH 4% TO BE ENRICHED AIR.
3. FLOOR SLABS ARE DESIGNED FOR FOLLOWING LOADING CONDITIONS:
 

	S.D.	L.L.
STAIRS & BALCONIES	0.50 kPa	4.80 kPa
LOCKERS & STORAGE	1.30 kPa	4.80 kPa
RESIDENTIAL	1.30 kPa	1.9 kPa
TOILETS	1.30 kPa	2.40 kPa
TERACES	5.0 kPa	4.80 kPa

\*


DIRECTION OF REINFORCING OF THE SLAB  
UNLESS DRAWING ON THE PLAN  
INDICATES OTHERWISE



FIRST FLOOR ELEV. 90.00m

NO.	REVISION	DATE
1	ISSUED FOR PERMIT	2014/02/20
2	REVISIONS FOR COMMENTS	2014/02/20
3	REVISIONS FOR COMMENTS	2014/02/20
4	REVISIONS FOR COMMENTS	2014/02/20
5	REVISIONS FOR COMMENTS	2014/02/20
6	REVISIONS FOR COMMENTS	2014/02/20
7	REVISIONS FOR COMMENTS	2014/02/20
8	REVISIONS FOR COMMENTS	2014/02/20
9	REVISIONS FOR COMMENTS	2014/02/20
10	REVISIONS FOR COMMENTS	2014/02/20
11	REVISIONS FOR COMMENTS	2014/02/20
12	REVISIONS FOR COMMENTS	2014/02/20
13	REVISIONS FOR COMMENTS	2014/02/20
14	REVISIONS FOR COMMENTS	2014/02/20
15	REVISIONS FOR COMMENTS	2014/02/20
16	REVISIONS FOR COMMENTS	2014/02/20
17	REVISIONS FOR COMMENTS	2014/02/20
18	REVISIONS FOR COMMENTS	2014/02/20
19	REVISIONS FOR COMMENTS	2014/02/20
20	REVISIONS FOR COMMENTS	2014/02/20

**Jablonsky, Ast and Ortner ENGINEERS**  
 1100 SHEPPARD AVENUE EAST  
 SUITE 200  
 SCARBOROUGH, ONTARIO M1S 1T5  
 TEL: 416-441-2777  
 FAX: 416-441-2778  
 E-MAIL: info@jablonsky.com



**ALEXANDRA PARK - BLOCK 11**  
 TORONTO, ONTARIO

DATE: 17/03/14  
 DRAWN BY: H.W.  
 CHECKED BY: H.W.  
 DATE: MARCH 2014