



| MOUNTING HEIGHT SCHEDULE<br>(DIMENSIONS ARE FROM FINISH FLOOR TO TOP OF WALL BOX) |                                                    |             |
|-----------------------------------------------------------------------------------|----------------------------------------------------|-------------|
| OUTLET                                                                            | SUITES                                             | PUBLIC AREA |
| RECEPTACLE                                                                        | 18" FFF                                            | 18" FFF     |
| KITCHEN COUNTER SPLIT RECEPTACLE                                                  | 46" FFF                                            | 46" FFF     |
| TV/TELEPHONE (MULTI-PORT) OUTLET                                                  | 18" FFF                                            | 18" FFF     |
| LIGHT SWITCH                                                                      | 38" FFF                                            | 38" FFF     |
| SECURITY PANEL                                                                    | 62" F.F.F                                          | 62" F.F.F   |
| WALL THERMOSTAT                                                                   | 62" F.F.F                                          | 62" F.F.F   |
| FRIDGE RECEPTACLE                                                                 | TO SUIT EQUIPMENT                                  |             |
| MICROWAVE/FAN UNIT RECEPTACLE                                                     | LOCATE IN UPPER CABINET ABOVE                      |             |
| UNDER CABINET LIGHTING RECEPTACLE                                                 | LOCATE IN UPPER CABINET ABOVE MICROWAVE / FAN UNIT |             |
| INTERCOM                                                                          |                                                    | 41" FFF     |
| FIREFIGHTER'S HANDSET                                                             |                                                    | 41" FFF     |
| PULL STATION                                                                      |                                                    | 41" FFF     |

- ### KEY NOTES RESIDENTIAL:
- ① FOR CIRCUITING, REFER TO TABLE #1.
  - ② PROVIDE ALARM SPEAKER, SMOKE DETECTOR AND RECEPTACLE AT EVERY THIRD FLOOR STAIR WELL STARTING FROM TOP FLOOR, AS PER TO DUG. E-32 FOR FIRE ALARM RISER DIAGRAM.
  - ③ REFER TO SUPERVISED VALVE AND FLOW SWITCH SCHEDULE ON DUG. E-30X FOR DETAILS ON TYPICAL FLOORS.
  - ④ PROVIDE TELECOMMUNICATION BACKBOARD C/W 15V, 1A 15A RECEPTACLE AS PER COMMUNICATION RISER DIAGRAM ON DUG. E-31.
  - ⑤ CONTRACTOR SHALL REFER TO ELECTRICAL SINGLE LINE DIAGRAM ON DUG. E-30 AND SDP RISER ON DUG. E-31 FOR SDP LOCATIONS AND DISTRIBUTION.
  - ⑥ PROVIDE CONDUIT AS PER RISER DETAIL #18 ON DUG. E-35 FOR BISSORTER/TRISSORTER CONTROL SYSTEM.
  - ⑦ ALL SUITE DOOR CONTACTS WILL COMPLETE WITH INTRUSION ALARM SYSTEM THAT CONTACT TO THE CONCERGE STATION
  - ⑧ DESIGNATED "LAUNDRY RECEPTACLE" AS DEFINED BY ESA CODE 26-110(e)(1) & 26-120(b) AND ESA BULLETIN 26-26-0 (WITHIN 3m RADIUS OF LAUNDRY CLOSET). RECEPTACLE SHALL BE CONNECTED TO A DEDICATED CIRCUIT. SEE DETAIL #14 ON DUG. E-35.
  - ⑨ INSTALL SIDE-MOUNTED RECEPTACLE ON KITCHEN ISLAND CABINET.

| LIFE SAFETY                                                                           |                                        |
|---------------------------------------------------------------------------------------|----------------------------------------|
|    | FIRE ALARM SMOKE DETECTOR              |
|    | SMOKE ALARM                            |
|    | FIRE ALARM DUCT TYPE SMOKE DETECTOR    |
|    | FIRE ALARM HEAT DETECTOR               |
|    | FIXED TEMP 68 °C DEGREE HEAT DETECTOR  |
|    | MOISTURE PROOF HEAT DETECTOR           |
|    | GO ALARM                               |
|   | COMBINATION SMOKE & GO ALARM           |
|  | GO SENSOR / NO SENSOR                  |
|  | FIRE ALARM MANUAL PULL STATION         |
|  | FIREFIGHTER'S WAND                     |
|  | FIRE ALARM STROBE HORN WALL MTD.       |
|  | FIRE ALARM MIN-HORN WALL MTD.          |
|  | FIRE ALARM SPEAKER/STROBE CEILING MTD. |
|  | FIRE ALARM SPEAKER CEILING MTD.        |
|  | FIRE ALARM ANNUNCIATOR PANEL           |
|  | FIRE ALARM CONTROL PANEL               |

**REVISIONS**

CONTRACTOR MUST CHECK AND VERIFY ALL DIMENSIONS AND CONDITIONS ON THE JOB AND REPORT DISCREPANCIES TO THE ENGINEERS BEFORE PROCEEDING WITH THE WORK. THIS DRAWING IS THE PROPERTY OF THE ENGINEERS AND MUST BE RETURNED UPON COMPLETION OF THE WORK.

DRAWINGS ARE NOT TO BE SCALED



PROJECT TITLE:  
ALEXANDRA PARK

|                   |                     |                |
|-------------------|---------------------|----------------|
| DRAWN BY:<br>S.O. | CHECKED BY:<br>S.T. | SCALE:<br>1:50 |
|-------------------|---------------------|----------------|

|         |                 |                 |
|---------|-----------------|-----------------|
| DATE:   | PROJECT NUMBER: | DRAWING NUMBER: |
| FEB, 13 | 1313            | E-12 OF         |