

TAG	TYPE	FAS.	Min.	S.C.	L.T.C.	NOM. THICKNES
P3 _ R1	92 METAL STUDS ACOUSTIC FURRING	-	-	-	NOTE 5	130
P3 _ Q2	INSULATED WALL	-	-	-	2.11	80
P3 _ Q1	INSULATED WALL	-	-	-	2.11	75
P3 _ L4	ELEVATOR / MECHANICAL / REFUSE SHAFT WALL	2.0 hr.	NOTE 6	S.C. 51	51	120
P3 _ L3	ELEVATOR / MECHANICAL / REFUSE SHAFT WALL	2.0 hr.	NOTE 6	S.C. 50	50	125
P3 _ L2	ELEVATOR / MECHANICAL / REFUSE SHAFT WALL	2.0 hr.	NOTE 6	S.C. 43	43	125
P3 _ L1	PIPE CHASE SHAFT WALL	1.0 hr.	NOTE 6	S.C. 39	39	120
P3 _ J1	ULC - W - 406 (Modified) DEMISING SUITE - to - SUITE	1.0 hr.	ULC-W-406	S.C. 45W	45W	230 MIN.

NOTE :
1. Max height = 4420 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
5. Refer to Acoustic Engineers Report for verification of STC values
6. Provide acoustic sealant to perimeter of entire wall, and continuously around all penetrations.

13 GREEN BOARD SHEETROCK
92 METAL STUDS @ 400 o.c. SPACED 25 from WALL
89 SOUND ATTENUATION BATTS
P1 (CONC.) OR P2 (CONC. BLOCK) WALL

NOTE :
1. Max height = n/a
2. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
3. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
4. Insulated wall may be used on either warm OR cold side of heated space.

16 CEMENTITIOUS SHEATHING
60 RIGID INSULATION, MIN. 2.11 R.S.I.
92 METAL SECUREMENT CHANNELS @ 400 o.c.
P1 (CONC.) or P2 (CONC. BLK.) WALL

NOTE :
1. Max height = n/a
2. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
3. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.

13 GYPSUM WALL BOARD
60 RIGID INSULATION, MIN. 2.11 R.S.I.
92 METAL SECUREMENT CHANNELS @ 400 o.c.
P1 (CONC.) or P2 (CONC. BLK.) WALL

NOTE :
1. Max height = 4560 ST25 (LO40)
2. Provide fire-sealant around entire perimeter of wall at junction between stud track and floor/ceiling, both sides of wall.
3. Penetrations must be protected to ensure continuity of fire separation.
4. Partial penetrations must be boxed out, or provided with approved fire-backing material (ie. perlite).
5. Thru-penetrations must be provided with an approved U.L.C. fire-stop and smoke-seal protection.
6. Refer to U.L.C.-W-403 for complete assembly requirements
7. U.L.C. Pre-Amble states ; "Additional layers of GWB may be added at any time."
8. U.L.C. Pre-Amble states ; "the dimension and gauge of steel studs are minimums. The hourly ratings apply when the steel studs are of a heavier gauge and/or larger dimension than specified in a design."
9. Gap between bottom of rated wall board and non-combustible slab and/or flooring surface may not exceed 12mm.

16 GYPSUM WALL BOARD
102 METAL STUDS @ 400 o.c.
16 GYPSUM WALL BOARD, FIRE-CODE 'C'

NOTE :
1. Max height = 6095 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. Refer to Acoustic Engineers Report for verification of STC values
4. Provide acoustic sealant to perimeter of entire wall, and continuously around all penetrations.

13 GYPSUM WALL BOARD
102 METAL STUDS @ 400 o.c.
13 GYPSUM WALL BOARD

NOTE :
1. Max height = 6095 ST25 (LO40)
2. Provide backer-board to tiled enclosures

16 GYPSUM WALL BOARD
102 METAL STUDS @ 400 o.c.
16 GYPSUM WALL BOARD

NOTE :
1. Max height = 6095 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
5. Refer to Acoustic Engineers Report for verification of STC values
6. Provide acoustic sealant to perimeter of entire wall, and continuously around all penetrations.

13 GYPSUM WALL BOARD
102 METAL STUDS @ 400 o.c.
13 GYPSUM WALL BOARD

NOTE :
1. Max height = 6095 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
5. Maintain continuous vapour barrier seal around perimeter of wall.

13 GYPSUM WALL BOARD
VAPOUR BARRIER
102 METAL STUDS @ 400 o.c. SPACED 15 from WALL
150 THERMAL INSULATION BATTS, MIN. 5.28 R.S.I.
BUILDING PAPER
P1 (CONC.) OR P2 (CONC. BLK.) WALL
or
102 MINERAL WOOL THERMAL INSULATION BLANKETS, MIN. 5.28 R.S.I.
P1 (CONC.) OR P2 (CONC. BLK.) WALL

NOTE :
1. Max height = 6095 ST25 (LO40)
2. Provide backer-board to tiled enclosures

13 GYPSUM WALL BOARD
102 METAL STUDS @ 400 o.c.
13 GYPSUM WALL BOARD

NOTE :
1. Max height = 6095 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
5. Maintain continuous vapour barrier seal around perimeter of wall.

13 GYPSUM WALL BOARD
VAPOUR BARRIER
102 METAL STUDS @ 400 o.c. SPACED 15 from WALL
150 THERMAL INSULATION BATTS, MIN. 5.28 R.S.I.
BUILDING PAPER
P1 (CONC.) OR P2 (CONC. BLK.) WALL
or
102 MINERAL WOOL THERMAL INSULATION BLANKETS, MIN. 5.28 R.S.I.
P1 (CONC.) OR P2 (CONC. BLK.) WALL

NOTE :
1. Max height = 6095 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
5. Maintain continuous vapour barrier seal around perimeter of wall.

13 GYPSUM WALL BOARD
VAPOUR BARRIER
64 METAL STUDS @ 400 o.c. SPACED 15 from WALL
89 THERMAL INSULATION BATTS, MIN. 2.3 R.S.I.
BUILDING PAPER
P1 (CONC.) OR P2 (CONC. BLK.) WALL
or
89 MINERAL WOOL THERMAL INSULATION BLANKETS, MIN. 2.3 R.S.I.
P1 (CONC.) OR P2 (CONC. BLK.) WALL

NOTE :
1. Max height = 3350 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
5. Maintain continuous vapour barrier seal around perimeter of wall.

13 GYPSUM WALL BOARD
64 METAL STUDS @ 400 o.c.
13 GYPSUM WALL BOARD

NOTE :
1. Max height = 3350 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
5. Maintain continuous vapour barrier seal around perimeter of wall.

13 GYPSUM WALL BOARD
VAPOUR BARRIER
64 METAL STUDS @ 400 o.c. SPACED 15 from WALL
89 THERMAL INSULATION BATTS, MIN. 2.3 R.S.I.
BUILDING PAPER
P1 (CONC.) OR P2 (CONC. BLK.) WALL
or
89 MINERAL WOOL THERMAL INSULATION BLANKETS, MIN. 2.3 R.S.I.
P1 (CONC.) OR P2 (CONC. BLK.) WALL

NOTE :
1. Max height = 3350 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
5. Maintain continuous vapour barrier seal around perimeter of wall.

13 GYPSUM WALL BOARD
VAPOUR BARRIER
64 METAL STUDS @ 400 o.c. SPACED 15 from WALL
89 THERMAL INSULATION BATTS, MIN. 2.3 R.S.I.
BUILDING PAPER
P1 (CONC.) OR P2 (CONC. BLK.) WALL
or
89 MINERAL WOOL THERMAL INSULATION BLANKETS, MIN. 2.3 R.S.I.
P1 (CONC.) OR P2 (CONC. BLK.) WALL

TAG	TYPE	FAS.	Min.	S.C.	L.T.C.	NOM. THICKNES
P3 _ E7	152 METAL STUDS GENERAL USE, FIRE-RATED	1 HR.	ULC-W406	S.C. -	-	185
P3 _ E6	152 METAL STUDS GENERAL USE, ACOUSTIC	-	-	-	51	180
P3 _ E5	152 METAL STUDS GENERAL USE	-	-	-	-	160
P3 _ E4	152 METAL STUDS INSULATED FURRING	-	-	-	3.6	180
P3 _ E3	152 METAL STUDS ACOUSTIC FURRING, SERVICE AREAS	-	-	-	NOTE 5	180
P3 _ E2	152 METAL STUDS ACOUSTIC FURRING	-	-	-	NOTE 5	180
P3 _ E1	152 METAL STUDS FURRING / PIPE SPACES	-	-	-	-	165

NOTE :
1. Max height = 4675 ST25 (LO40)
2. Provide dens/glass to tiled enclosures
3. Refer to Acoustic Engineer's Report for verification of STC values
4. Provide acoustic sealant to perimeter of entire wall, and continuously around all penetrations.
5. Partial penetrations must be boxed out, or provided with approved fire-backing material (ie. perlite).
6. Thru-penetrations must be provided with an approved U.L.C. fire-stop and smoke-seal protection.
7. Refer to U.L.C.-W-403 for complete assembly requirements

16 GYPSUM WALL BOARD, FIRE-CODE 'C'
92 METAL STUDS @ 400 o.c.
16 GYPSUM WALL BOARD, FIRE-CODE 'C'

NOTE :
1. Max height = 4675 ST25 (LO40)
2. Provide dens/glass to tiled enclosures

13 GYPSUM WALL BOARD
92 METAL STUDS @ 400 o.c.
13 GYPSUM WALL BOARD

NOTE :
1. Max height = 4675 ST25 (LO40)
2. Provide dens/glass to tiled enclosures

13 GYPSUM WALL BOARD
92 METAL STUDS @ 400 o.c.
13 GYPSUM WALL BOARD

NOTE :
1. Max height = 4420 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
5. Refer to Acoustic Engineers Report for verification of STC values
6. Provide acoustic sealant to perimeter of entire wall, and continuously around all penetrations.

13 GYPSUM WALL BOARD
92 METAL STUDS @ 400 o.c.
13 GYPSUM WALL BOARD

NOTE :
1. Max height = 4420 ST25 (LO40)
2. Provide dens/glass to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
5. Refer to Acoustic Engineers Report for verification of STC values
6. Provide acoustic sealant to perimeter of entire wall, and continuously around all penetrations.

13 GYPSUM WALL BOARD
92 METAL STUDS @ 400 o.c.
13 GYPSUM WALL BOARD

NOTE :
1. Max height = 4420 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
5. Refer to Acoustic Engineers Report for verification of STC values
6. Provide acoustic sealant to perimeter of entire wall, and continuously around all penetrations.

13 GYPSUM WALL BOARD
92 METAL STUDS @ 400 o.c.
13 GYPSUM WALL BOARD

NOTE :
1. Max height = 3810 ST25 (LO40)
2. Provide fire-sealant around entire perimeter of wall at junction between stud track and floor/ceiling, both sides of wall.
3. Penetrations must be protected to ensure continuity of fire separation.
4. Partial penetrations must be boxed out, or provided with approved fire-backing material (ie. perlite).
5. Thru-penetrations must be provided with an approved U.L.C. fire-stop and smoke-seal protection.
6. Refer to U.L.C.-W-403 for complete assembly requirements.

16 GYPSUM WALL BOARD, FIRE-CODE 'C'
44 METAL STUDS @ 400 o.c.
16 GYPSUM WALL BOARD, FIRE-CODE 'C'

NOTE :
1. Max height = 3810 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
5. Refer to Acoustic Engineers Report for verification of STC values
6. Provide acoustic sealant to perimeter of entire wall, and continuously around all penetrations.

13 GYPSUM WALL BOARD
64 METAL STUDS @ 400 o.c.
50 SOUND ATTENUATION BATTS
13 GYPSUM WALL BOARD

NOTE :
1. Max height = 3810 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
5. Refer to Acoustic Engineers Report for verification of STC values
6. Provide acoustic sealant to perimeter of entire wall, and continuously around all penetrations.

13 GYPSUM WALL BOARD
64 METAL STUDS @ 400 o.c.
13 GYPSUM WALL BOARD

NOTE :
1. Max height = 3350 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.
5. Maintain continuous vapour barrier seal around perimeter of wall.

13 GYPSUM WALL BOARD
VAPOUR BARRIER
64 METAL STUDS @ 400 o.c. SPACED 15 from WALL
89 THERMAL INSULATION BATTS, MIN. 2.3 R.S.I.
BUILDING PAPER
P1 (CONC.) OR P2 (CONC. BLK.) WALL
or
89 MINERAL WOOL THERMAL INSULATION BLANKETS, MIN. 2.3 R.S.I.
P1 (CONC.) OR P2 (CONC. BLK.) WALL

TAG	TYPE	FAS.	Min.	S.C.	L.T.C.	NOM. THICKNES
P3 _ D7	92 METAL STUDS GENERAL USE, FIRE-RATED	1 HR.	ULC-W 407	-	-	125
P3 _ D6	92 METAL STUDS GENERAL USE, ACOUSTIC	-	-	-	51	120
P3 _ D5	92 METAL STUDS GENERAL USE	-	-	-	-	120
P3 _ D4	92 METAL STUDS INSULATED FURRING	-	-	-	2.3	120
P3 _ D3	92 METAL STUDS ACOUSTIC FURRING SERVICE AREAS	-	-	-	NOTE 5	125
P3 _ D2	92 METAL STUDS ACOUSTIC FURRING	-	-	-	NOTE 5	120
P3 _ D1	92 METAL STUDS FURRING / PIPE SPACES	-	-	-	-	105
P3 _ C6	64 METAL STUDS GENERAL USE, FIRE-RATED	1.0 hr.	ULC-W406	S.C. -	-	95
P3 _ C5	64 METAL STUDS GENERAL USE, ACOUSTIC	-	-	-	47	90
P3 _ C4	64 METAL STUDS GENERAL USE	-	-	-	-	90
P3 _ C3	64 METAL STUDS INSULATED FURRING	-	-	-	2.3	90
P3 _ C2	64 METAL STUDS ACOUSTIC FURRING	-	-	-	NOTE 5	95
P3 _ C1	64 METAL STUDS FURRING / PIPE SPACES	-	-	-	-	80
P3 _ B4	41 METAL STUDS GENERAL USE	-	-	-	-	70
P3 _ B3	41 METAL STUDS INSULATED FURRING	-	-	-	1.4	NOTE 5 70
P3 _ B2	41 METAL STUDS ACOUSTIC FURRING	-	-	-	NOTE 5	70
P3 _ B1	41 METAL STUDS FURRING / PIPE SPACES	-	-	-	-	55
P3 _ A5	RESILIENT METAL CHANNELS ACOUSTIC	-	NOTE 3	-	VARIES	45
P3 _ A4	RESILIENT METAL CHANNELS ACOUSTIC	-	NOTE 3	-	VARIES	30
P3 _ A3	FURRING CHANNELS ACOUSTIC	-	-	-	VARIES	30
P3 _ A2	FURRING CHANNELS	-	-	-	-	40
P3 _ A1	LAMINATED DRYWALL	-	-	-	-	15

NOTE :
1. Max height = 3350 ST25 (LO40)
2. Provide backer-board to tiled enclosures
3. All concrete form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
4. Continuity of fire-separation through back-up concrete structure, or concrete block walls to be verified prior to covering/concealing in any way.

13 GYPSUM WALL BOARD
64 METAL STUDS @ 400 o.c.
13 GYPSUM WALL BOARD

NOTE :
FOR SUITE CEILING HEIGHT SOLID AT 3000mm
41 METAL STUDS FOR PARTITION P3-B4
TO BE @ 300mm O.C.

NOTE :
ARTISCAPE / AFFORDABLE COMPONENT
ABUSE RESISTANT DRYWALL TO BE USED ON ALL ARTISCAPE / AFFORDABLE LOBBY AND CORRIDOR WALLS

13 GYPSUM WALL BOARD
41 METAL STUDS @ 400 o.c.
13 GYPSUM WALL BOARD

NOTE :
FOR SUITE CEILING HEIGHT SOLID AT 3000mm
41 METAL STUDS FOR PARTITION P3-B1
TO BE @ 300mm O.C.

NOTE :
ARTISCAPE / AFFORDABLE COMPONENT
ABUSE RESISTANT DRYWALL TO BE USED ON ALL ARTISCAPE / AFFORDABLE LOBBY AND CORRIDOR WALLS

2 LAYERS, 13 GYPSUM WALL BOARD
16 RESILIENT METAL CHANNELS @ 600 o.c.
20 SOUND ATTENUATION BATTS
P1 (CONC.) or P2 (CONC. BLK.) WALL

NOTE :
ARTISCAPE / AFFORDABLE COMPONENT
ABUSE RESISTANT DRYWALL TO BE USED ON ALL ARTISCAPE / AFFORDABLE LOBBY AND CORRIDOR WALLS

13 GYPSUM WALL BOARD
16 RESILIENT METAL CHANNELS 600 O.C.
25 SOUND ATTENUATION BATTS
P1 (CONC.) or P2 (CONC. BLK.) WALL

NOTE :
ARTISCAPE / AFFORDABLE COMPONENT
ABUSE RESISTANT DRYWALL TO BE USED ON ALL ARTISCAPE / AFFORDABLE LOBBY AND CORRIDOR WALLS

13 GYPSUM WALL BOARD
16 RESILIENT METAL CHANNELS
P1 (CONC.) or P2 (CONC. BLK.) WALL

NOTE :
ARTISCAPE / AFFORDABLE COMPONENT
ABUSE RESISTANT DRYWALL TO BE USED ON ALL ARTISCAPE / AFFORDABLE LOBBY AND CORRIDOR WALLS

13 GYPSUM WALL BOARD
25 METAL FURRING CHANNELS @ 400 O.C.
P1 (CONC.) or P2 (CONC. BLK.) WALL

NOTE :
ARTISCAPE / AFFORDABLE COMPONENT
ABUSE RESISTANT DRYWALL TO BE USED ON ALL ARTISCAPE / AFFORDABLE LOBBY AND CORRIDOR WALLS

13 GYPSUM WALL BOARD LAMINATED TO
P1 (CONC.) or P2 (CONC. BLK.) WALL TYPE.

TAG	TYPE	FAS.	Min.	S.C.	L.T.C.	NOM. THICKNES
P3 _ C2	64 METAL STUDS ACOUSTIC FURRING	-	-	-	NOTE 5	95
P3 _ C1	64 METAL STUDS FURRING / PIPE SPACES	-	-	-	-	80
P3 _ B4	41 METAL STUDS GENERAL USE	-	-	-	-	70
P3 _ B3	41 METAL STUDS INSULATED FURRING	-	-	-	1.4	NOTE 5 70
P3 _ B2	41 METAL STUDS ACOUSTIC FURRING	-	-	-	NOTE 5	70
P3 _ B1	41 METAL STUDS FURRING / PIPE SPACES	-	-	-	-	55
P3 _ A5	RESILIENT METAL CHANNELS ACOUSTIC	-	NOTE 3	-	VARIES	45
P3 _ A4	RESILIENT METAL CHANNELS ACOUSTIC	-	NOTE 3	-	VARIES	30
P3 _ A3	FURRING CHANNELS ACOUSTIC	-	-	-	VARIES	30
P3 _ A2	FURRING CHANNELS	-	-	-	-	40
P3 _ A1	LAMINATED DRYWALL	-	-	-	-	15

NOTE :
1. Maximum height guideline is 5340 (non-load bearing), 2900 (load bearing)
2. Refer to Structural Engineering drawings for lateral support details and maximum height spans.
3. Thru-penetrations must be protected by approved ULC fire-stop assemblies to ensure continuity of fire-separation.
4. Partial penetrations are NOT permitted.
5. Provide mineral wool fire-stopping and smoke-seal caulk at gap between top of block and underside of structure above.
6. Continuity of fire-separation to be verified prior to covering/concealing in any way.
7. Refer to Acoustic Engineers Report for verification of STC values
8. Provide acoustic sealant to perimeter of entire wall, and continuously around all penetrations.

FIRE-RATING :
9. Refer to individual block assemblies for F.R.R. testing references.

Refer to A6 / P2 | B2
50 ACOUSTIC INSULATION BOARD

NOTE :
1. Maximum height guideline is 6940 (non-load bearing), 3900 (load bearing)
2. Refer to Structural Engineering drawings for lateral support details and maximum height spans.
3. Thru-penetrations must be protected by approved ULC fire-stop assemblies to ensure continuity of fire-separation.
4. Partial penetrations are NOT permitted.
5. Provide mineral wool fire-stopping and smoke-seal caulk at gap between top of block and underside of structure above.
6. Continuity of fire-separation to be verified prior to covering/concealing in any way.

FIRE-RATING :
7a. N.B.C. 2010 Table 5.2.1.1 for Type C or N Concrete (O.B.C. 2012 SB-2 Table 2.1.1 for Type C or N Concrete)
7b. ULC 1395 - Type I (4.00) Concrete; ULC tested supplies ONLY 2.0 hr. F.R.R.

190 CONCRETE BLOCK , STANDARD HOLLOW (56% SOLID) WITH MINIMUM 2 COATS OF PAINT TO UNFINISHED SIDE (as per O.B.C. SB-3 TABLE 1 NOTE 3) WHERE STC IS REQUIRED.

NOTE :
1. Maximum height guideline is 6940 (non-load bearing), 3900 (load bearing)
2. Refer to Structural Engineering drawings for lateral support details and maximum height spans.
3. Thru-penetrations must be protected by approved ULC fire-stop assemblies to ensure continuity of fire-separation.
4. Partial penetrations are NOT permitted.
5. Provide mineral wool fire-stopping and smoke-seal caulk at gap between top of block and underside of structure above.
6. Continuity of fire-separation to be verified prior to covering/concealing in any way.

FIRE-RATING :
7a. N.B.C. 2010 Table 5.2.1.1 for Type C or N Concrete (O.B.C. 2012 SB-2 Table 2.1.1 for Type C or N Concrete)
7b. ULC 554 - Type N/S Concrete; ULC Tested Supplies ONLY 2.0 hr F.R.R.

190 CONCRETE BLOCK , 75% SOLID (75% SOLID) WITH MINIMUM 2 COATS OF PAINT TO UNFINISHED SIDE (as per O.B.C. SB-3 TABLE 1 NOTE 3) WHERE STC IS REQUIRED.

NOTE :
1. Maximum height guideline is 6940 (non-load bearing), 3900 (load bearing)
2. Refer to Structural Engineering drawings for lateral support details and maximum height spans.
3. Thru-penetrations must be protected by approved ULC fire-stop assemblies to ensure continuity of fire-separation.
4. Partial penetrations are NOT permitted.
5. Provide mineral wool fire-stopping and smoke-seal caulk at gap between top of block and underside of structure above.
6. Continuity of fire-separation to be verified prior to covering/concealing in any way.

FIRE-RATING :
7a. N.B.C. 2010 Table 5.2.1.1 for Type C or N Concrete (O.B.C. 2012 SB-2 Table 2.1.1 for Type C or N Concrete)
7b. ULC 1395 - Type I (4.00) Concrete; ULC tested supplies ONLY 2.0 hr. F.R.R.

190 CONCRETE BLOCK , STANDARD HOLLOW (56% SOLID) WITH MINIMUM 2 COATS OF PAINT TO UNFINISHED SIDE (as per O.B.C. SB-3 TABLE 1 NOTE 3) WHERE STC IS REQUIRED.

NOTE :
1. Maximum height guideline is 6940 (non-load bearing), 3900 (load bearing)
2. Refer to Structural Engineering drawings for lateral support details and maximum height spans.
3. Thru-penetrations must be protected by approved ULC fire-stop assemblies to ensure continuity of fire-separation.
4. Partial penetrations are NOT permitted.
5. Provide mineral wool fire-stopping and smoke-seal caulk at gap between top of block and underside of structure above.
6. Continuity of fire-separation to be verified prior to covering/concealing in any way.

FIRE-RATING :
7a. N.B.C. 2010 Table 5.2.1.1 for Type C or N Concrete (O.B.C. 2012 SB-2 Table 2.1.1 for Type C or N Concrete)
7b. ULC 554 - Type N/S Concrete; ULC Tested Supplies ONLY 2.0 hr F.R.R.

140 CONCRETE BLOCK , STANDARD HOLLOW (56% SOLID) WITH MINIMUM 2 COATS OF PAINT TO UNFINISHED SIDE (as per O.B.C. SB-3 TABLE 1 NOTE 3) WHERE STC IS REQUIRED.

NOTE :
1. Maximum height guideline is 5340 (non-load bearing), 2900 (load bearing)
2. Refer to Structural Engineering drawings for lateral support details and maximum height spans.
3. Thru-penetrations must be protected by approved ULC fire-stop assemblies to ensure continuity of fire-separation.
4. Partial penetrations are NOT permitted.
5. Provide mineral wool fire-stopping and smoke-seal caulk at gap between top of block and underside of structure above.
6. Continuity of fire-separation to be verified prior to covering/concealing in any way.

FIRE-RATING :
7. N.B.C. 2010 Table 5.2.1.1 for Type C or N Concrete (O.B.C. 2012 SB-2 Table 2.1.1 for Type C or N Concrete)

140 CONCRETE BLOCK , 75% SOLID - GENERAL USE

NOTE :
1. Maximum height guideline is 5340 (non-load bearing), 2900 (load bearing)
2. Refer to Structural Engineering drawings for lateral support details and maximum height spans.
3. Thru-penetrations must be protected by approved ULC fire-stop assemblies to ensure continuity of fire-separation.
4. Partial penetrations are NOT permitted.
5. Provide mineral wool fire-stopping and smoke-seal caulk at gap between top of block and underside of structure above.
6. Continuity of fire-separation to be verified prior to covering/concealing in any way.

FIRE-RATING :
7. N.B.C. 2010 Table 5.2.1.1 for Type C or N Concrete (O.B.C. 2012 SB-2 Table 2.1.1 for Type C or N Concrete)

140 CONCRETE BLOCK, 20% SOLID) WITH MINIMUM 2 COATS OF PAINT TO UNFINISHED SIDE (as per O.B.C. SB-3 TABLE 1 NOTE 3) WHERE STC IS REQUIRED.

NOTE :
1. Maximum height guideline is 5340 (non-load bearing), 2900 (load bearing)
2. Refer to Structural Engineering drawings for lateral support details and maximum height spans.
3. Thru-penetrations must be protected by approved ULC fire-stop assemblies to ensure continuity of fire-separation.
4. Partial penetrations are NOT permitted.
5. Provide mineral wool fire-stopping and smoke-seal caulk at gap between top of block and underside of structure above.
6. Continuity of fire-separation to be verified prior to covering/concealing in any way.

FIRE-RATING :
7. N.B.C. 2010 Table 5.2.1.1 for Type C or N Concrete (O.B.C. 2012 SB-2 Table 2.1.1 for Type C or N Concrete)

140 CONCRETE BLOCK, STANDARD HOLLOW (56% SOLID) WITH MINIMUM 2 COATS OF PAINT TO UNFINISHED SIDE (as per O.B.C. SB-3 TABLE 1 NOTE 3) WHERE STC IS REQUIRED.

NOTE :
1. Maximum height guideline is 5340 (non-load bearing), 2900 (load bearing)
2. Refer to Structural Engineering drawings for lateral support details and maximum height spans.
3. Thru-penetrations must be protected by approved ULC fire-stop assemblies to ensure continuity of fire-separation.
4. Partial penetrations are NOT permitted.
5. Provide mineral wool fire-stopping and smoke-seal caulk at gap between top of block and underside of structure above.
6. Continuity of fire-separation to be verified prior to covering/concealing in any way.

FIRE-RATING :
7. N.B.C. 2010 Table 5.2.1.1 for Type C or N Concrete (O.B.C. 2012 SB-2 Table 2.1.1 for Type C or N Concrete)

140 CONCRETE BLOCK, STANDARD HOLLOW (56% SOLID) WITH MINIMUM 2 COATS OF PAINT TO UNFINISHED SIDE (as per O.B.C. SB-3 TABLE 1 NOTE 3) WHERE STC IS REQUIRED.

NOTE :
1. Maximum height guideline is 5340 (non-load bearing), 2900 (load bearing)
2. Refer to Structural Engineering drawings for lateral support details and maximum height spans.
3. Thru-penetrations must be protected by approved ULC fire-stop assemblies to ensure continuity of fire-separation.
4. Partial penetrations are NOT permitted.
5. Provide mineral wool fire-stopping and smoke-seal caulk at gap between top of block and underside of structure above.
6. Continuity of fire-separation to be verified prior to covering/concealing in any way.

FIRE-RATING :
7. N.B.C. 2010 Table 5.2.1.1 for Type C or N Concrete (O.B.C. 2012 SB-2 Table 2.1.1 for Type C or N Concrete)

90 CONCRETE BLOCK, STANDARD HOLLOW (73% SOLID) WITH MINIMUM 2 COATS OF PAINT TO UNFINISHED SIDE (as per O.B.C. SB-3 TABLE 1 NOTE 3) WHERE STC IS REQUIRED.

NOTE :
1. Refer to Structural Engineering Drawings for additional performance criteria.
2. All form tie-holes to be filled with mineral wool fire-stop and ULC Rated fire-sealants.
3. Continuity of fire-separation around all thru-penetrations to be maintained by ULC-approved fire-stop assembly.
4. Partial penetrations, whereby full thickness of concrete structure is reduced, are not permitted as effective fire-rating is also reduced.
5. Continuity of fire-separation to be verified prior to covering concrete structure in any way.

CAST-IN-PLACE CONCRETE STRUCTURE
(Refer to Structural Engineering Drawings)

ZOOMED

TAG	TYPE	FAS.	Min.	S.C.	L.T.C.	NOM. THICKNES
P2 _ F2	LIGHTWEIGHT CONCRETE BLOCK CHILLER / GENERATOR ROOMS	2.0 hr.	Note 9	S.C. 55	Note 7	190
P2 _ F1	LIGHTWEIGHT CONCRETE BLOCK CHILLER / GENERATOR ROOMS	2.0 hr.	Note 9	S.C. 55	Note 7	330
P2 _ C3	190 CONCRETE BLOCK, LIGHTWEIGHT GENERAL USE	2.0hr.	Note 7	106	48	190
P2 _ C2	190 CONCRETE BLOCK 75% SOLID - GENERAL USE	3.0 hr.	Note 7	148	51	190
P2 _ C1	190 CONCRETE BLOCK STANDARD GENERAL USE	1.5 hr.	Note 7	106	48	190
P2 _ B3	140 CONCRETE BLOCK, LIGHTWEIGHT GENERAL USE	1.5 hr.	Note 7	81	48	140
P2 _ B2	140 CONCRETE BLOCK 75% SOLID - GENERAL USE	2.0 hr	Note 7	112	48	140
P2 _ B1	140 CONCRETE BLOCK STANDARD GENERAL USE	1.5 hr.	Note 7	81	48	140
P2 _ A2	90 CONCRETE BLOCK STANDARD GENERAL USE	45 min	Note 7	66	48	90
P1 _ A1	UNFINISHED STRUCTURE	2.0 hr.	NO FAS ASSEMBLY	-	-	200 MIN.

NOTE :
1. Max height = 4660 ST25 (LO40)
2. Provide continuous acoustic sealant to entire perimeter of wall, on suite side of wall, and continuously around all penetrations.
3. Refer to Acoustic Engineer's Report for verification of STC values.
4. Penetrations must be protected by approved ULC fire-stop assemblies to ensure continuity of fire separation.
5. Partial penetrations must be boxed out, or provided with ULC approved fire-backing material (ie. perlite).
6. Refer to ULC-W-403 for complete assembly requirements
7. ULC Pre-Amble states ; "Additional layers of GWB may be added at any time."
8. ULC Pre-Amble states ; "the dimension and gauge of steel studs are minimums. The hourly ratings apply when the steel studs are of a heavier gauge and/or larger dimension than specified in a design."
9. Gap between bottom of rated wall board and non-combustible slab and/or flooring surface may not exceed 12mm.

16 GYPSUM WALL BOARD, FIRE-CODE 'C' (see NOTE-7)
92 METAL STUDS @ 600 o.c. (see NOTE-6)
89 MINERAL WOOL S.A.F.B. INSULATION
16 GYPSUM WALL BOARD, FIRE-CODE 'C'

NOTE :
ARTISCAPE / AFFORDABLE COMPONENT
ABUSE RESISTANT DRYWALL TO BE USED ON ALL ARTISCAPE / AFFORDABLE LOBBY AND CORRIDOR WALLS

| TAG | TYPE | FAS. | Min. | S.C.