

ELEVATION VIEW



FLOOR PLAN VIEW

Interior East Elevation - Part 1 (22 / A4-15)
Scale: 1 : 50



ELEVATION VIEW



FLOOR PLAN VIEW

Interior West Elevation - Part 1 (21 / A4-15)
Scale: 1 : 50



Interior East Elevation - Part 4 (20 / A4-15)
Scale: 1 : 50



Interior East Elevation - Part 3 (19 / A4-15)
Scale: 1 : 50



Interior East Elevation - Part 2 (18 / A4-15)
Scale: 1 : 50



ELEVATION VIEW



FLOOR PLAN VIEW

Interior East Elevation - Part 1 (17 / A4-15)
Scale: 1 : 50



Window Schedule Partial Floor Plan - Level 3 (7 / A4-15)
Scale: 1 : 100



West Elevation - Part 20 (9 / A4-15)
Scale: 1 : 50



West Elevation - Part 19 (8 / A4-15)
Scale: 1 : 50



Window Schedule Key Plan - Level 4 (6 / A4-15)
NTS



Window Schedule Partial Floor Plan - Level 4 (5 / A4-15)
Scale: 1 : 100



Window Schedule Partial Floor Plan - Level 2 (4 / A4-15)
Scale: 1 : 100



Window Schedule Key Plan - Level 2-3 (2 / A4-15)
NTS

WINDOW SCHEDULE LEGEND

13148 - AQUAVISTA
UPDATED: FEBRUARY 16, 2016

3 — **PREFINISHED ALUMINUM WINDOW WALL - VISION PANEL**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
GLASS TYPE: CLEAR INNER & OUTER LITE, GUARDIAN SUNGUARD - SUPERNEUTRAL SN64 ON SURFACE 2

3A — **PREFINISHED ALUMINUM WINDOW WALL - VISION PANEL FRIT PATTERN**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
GLASS TYPE: CLEAR INNER & OUTER LITE, GUARDIAN SUNGUARD - SUPERNEUTRAL SN64 ON SURFACE 2; WHITE FRIT SBM DIAMETER DOTS IN NOVA SQUARE PATTERN ON SURFACE 2

3B — **PREFINISHED ALUMINUM WINDOW WALL - OPERABLE AWNING**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
GLASS TYPE: CLEAR INNER & OUTER LITE, GUARDIAN SUNGUARD - SUPERNEUTRAL SN64 ON SURFACE 2

3C — **PREFINISHED ALUMINUM WINDOW WALL - OPERABLE AWNING FRIT PATTERN**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
GLASS TYPE: CLEAR INNER & OUTER LITE, GUARDIAN SUNGUARD - SUPERNEUTRAL SN64 ON SURFACE 2; WHITE FRIT SBM DIAMETER DOTS IN NOVA SQUARE PATTERN ON SURFACE 2

3D — **PREFINISHED ALUMINUM WINDOW WALL - GLASS SPANDREL PANEL**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
GLASS TYPE: CLEAR PLCAST
COLOUR: SOLID FRIT VIRACON SUBDUED GRAY V903 ON SURFACE 2

3E — **PREFINISHED ALUMINUM WINDOW WALL - METAL SPANDREL PANEL**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
METAL PANEL: PPG UC7521HF DURANAR GREY VELVET

3F — **PREFINISHED ALUMINUM WINDOW WALL - METAL LOUVER**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
METAL LOUVER: PPG UC7521HF DURANAR GREY VELVET

3G1 — **PREFINISHED ALUMINUM WINDOW WALL - METAL SLAB COVER - PROFILE 40x420mm**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
SLAB COVER: PPG UC1687SSL DURANAR XL STEEL SILVER CITY

3G2 — **PREFINISHED ALUMINUM WINDOW WALL - METAL SLAB COVER - PROFILE 105x420mm**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
SLAB COVER: PPG UC1687SSL DURANAR XL STEEL SILVER CITY

3G3 — **PREFINISHED ALUMINUM WINDOW WALL - METAL SLAB COVER - PROFILE 220x420mm**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
SLAB COVER: PPG UC1687SSL DURANAR XL STEEL SILVER CITY

3H — **PREFINISHED ALUMINUM WINDOW WALL - OPERABLE WINDOW - VISION PANEL**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
GLASS TYPE: CLEAR INNER & OUTER LITE, GUARDIAN SUNGUARD - SUPERNEUTRAL SN64 ON SURFACE 2

3J — **PREFINISHED ALUMINUM WINDOW WALL - OPERABLE WINDOW - GLASS SPANDREL PANEL**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
GLASS TYPE: CLEAR PLCAST
COLOUR: SOLID FRIT VIRACON SUBDUED GRAY V903 ON SURFACE 2

3K — **PREFINISHED ALUMINUM WINDOW WALL - OPERABLE WINDOW - METAL LOUVER**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
METAL LOUVER: PPG UC7521HF DURANAR GREY VELVET

4 — **PREFINISHED STOREFRONT CURTAINWALL - VISION PANEL (GROUND FLOOR)**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
GLASS TYPE: CLEAR INNER & OUTER LITE, GUARDIAN SUNGUARD - SUPERNEUTRAL SN64 ON SURFACE 2

4A — **PREFINISHED STOREFRONT CURTAINWALL - VISION PANEL FRIT PATTERN (GROUND FLOOR)**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
GLASS TYPE: CLEAR INNER & OUTER LITE, GUARDIAN SUNGUARD - SUPERNEUTRAL SN64 ON SURFACE 2; WHITE FRIT SBM DIAMETER DOTS IN NOVA SQUARE PATTERN ON SURFACE 2

4B — **PREFINISHED STOREFRONT CURTAINWALL - SHADOW BOX (GROUND FLOOR)**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
GLASS TYPE: CLEAR INNER & OUTER LITE, GUARDIAN SUNGUARD - SUPERNEUTRAL SN64 ON SURFACE 2
COLOUR: WHITE COLOUR PAINT ON ALUMINUM PAN BEHIND SURFACE 4

4C — **PREFINISHED STOREFRONT CURTAINWALL - GLASS SPANDREL PANEL (GROUND FLOOR)**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
GLASS TYPE: CLEAR INNER & OUTER LITE, GUARDIAN SUNGUARD - SUPERNEUTRAL SN64 ON SURFACE 2
COLOUR: SOLID FRIT GREY VELVET ON SURFACE 2

4D — **PREFINISHED STOREFRONT CURTAINWALL - METAL LOUVER (GROUND FLOOR)**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
METAL LOUVER: PPG UC7521HF DURANAR GREY VELVET

4E — **PREFINISHED STOREFRONT CURTAINWALL - METAL SPANDREL PANEL (GROUND FLOOR)**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
METAL PANEL: PPG UC7521HF DURANAR GREY VELVET

4F — **PREFINISHED STOREFRONT CURTAINWALL - VISION PANEL FRIT PATTERN (GROUND FLOOR)**
ALUM. COLOUR: EXTERIOR - PPG UC7521HF DURANAR GREY VELVET; INTERIOR - #1295 DURACRON WHITE
GLASS TYPE: CLEAR INNER & OUTER LITE, GUARDIAN SUNGUARD - SUPERNEUTRAL SN64 ON SURFACE 3; GREY VELVET HORIZONTAL FRIT PATTERN ON SURFACE 2

TYPICAL WINDOW SCHEDULE NOTES:

1. ADD 10MM CAULKING ALLOWANCE ON ONE OR BOTH SIDES OF WINDOW OPENING.
2. ALL DOOR AND WINDOW TAPINGS AS PER PLANS AND ELEVATIONS.
3. CO-ORDINATE LOUVER LOCATIONS WITH MECHANICAL DRAWINGS.
4. CO-ORDINATE ALL WINDOW WALL WITH ROOF, WALL AND FLOOR CONSTRUCT
5. CO-ORDINATE BALCONY/TERRACE ELECTRICAL OUTLETS WITH ELECTRICAL DRAWINGS.

OBC REQUIREMENTS:

9.7.2 WINDOW STANDARDS
(1) WINDOWS SHALL CONFORM TO:
(a) WINDOWS SHALL CONFORM TO CAN/CGSB-12.8M, "INSULATING GLASS UNIT"; AND
(b) THE CAN/CSA-A440.1, "USER SELECTION GUIDE TO CSA STANDARD CAN/CSA-A440.0/.00 WINDOWS".
9.7.3 GLASS
9.7.3.1 GLASS STANDARDS
(1) GLASS SHALL CONFORM TO:
(a) CAN/CGSB-12.1M, "SPECIFICATION FOR LAMINATED SAFETY GLASS",
(b) CAN/CGSB-12.2-M, "FLAT, CLEAR FLOAT GLASS",
(c) CAN/CGSB-12.3-M, "FLAT, TINTED FLOAT GLASS",
(d) CAN/CGSB-12.4-M, "HEAT TREATED FLAT GLASS",
(e) CAN/CGSB-12.8, "INSULATING GLASS UNITS",
(f) CAN/CGSB-12.10-M, "GLASS, LIGHT AND HEAT-REFLECTING",
(g) CAN/CGSB-12.11-M, "WIRED SAFETY GLASS", AND
(h) ASTM E2190, "INSULATING GLASS UNIT PERFORMANCE AND EVALUATION".
9.7.3.2 STRUCTURAL DESIGN OF GLASS
(1) EXCEPT AS PERMITTED IN SENTENCE (2), GLAZING AND SKYLIGHTS SHALL BE DESIGNED IN CONFORMANCE WITH CAN/CSA-S 23.94.
STRUCTURAL DESIGN OF GLASS FOR BUILDINGS"
9.7.4.1 SEALING COMPOUND
(1) SEALING COMPOUND USED TO SEAL THE GLASS COMPONENT OF A FACTORY-SEALED DOUBLE-GLAZED UNIT TO THE DASH COMPONENT SHALL BE COMPATIBLE WITH THE MATERIAL USED TO EDGE SEAL THE GLASS COMPONENTS.

9.7.6.4 WINDOWS ABOVE THE SECOND STOREY
(5) WINDOWS IN PUBLIC AREAS THAT EXTEND TO LESS THAN 1 000 MM FROM THE FLOOR AND ARE LOCATED ABOVE THE SECOND STOREY IN BUILDINGS OF RESIDENTIAL OCCUPANCY SHALL BE,
(a) PROTECTED BY A GUARD CONFORMING TO SENTENCES 9.8.8., OR
(b) NON-OPENABLE AND DESIGNED TO WITHSTAND THE LATERAL DESIGN LOADS FOR GUARDS AS PROVIDED IN ARTICLES 4.1.5.15. OR 9.8.8.2
9.7.6.5 RESISTANCE TO FORCED ENTRY
9.7.6.1 FORCED ENTRY THROUGH WINDOWS
(1) IN DWELLING UNITS, WINDOWS, ANY PART OF WHICH IS LOCATED WITHIN 2 000 MM OF ADJACENT GROUND LEVEL, SHALL CONFORM TO CAN/CSA-A440.2/A440.3, "WINDOWS" FOR RESISTANCE TO FORCED ENTRY AS DESCRIBED IN CLAUSE 10.7.9 OF CAN/CSA-A440.M, "WINDOWS".

9.8.8.1 REQUIRED GUARDS
(1) EXCEPT AS PERMITTED IN SENTENCES (2) AND (3), EVERY SURFACE TO WHICH ACCESS IS PROVIDED FOR OTHER THAN MAINTENANCE PURPOSES, INCLUDING BUT NOT LIMITED TO FLOORS OR STEPS AND RAMPS, EXTERIOR LANDINGS, PORCHES, BALCONIES, GALLERIES AND RAISED, SHALL BE PROTECTED BY A GUARD ON EACH SIDE THAT IS NOT PROTECTED BY A WALL FOR THE LENGTH WHERE,
(a) THE ADJACENT SURFACE IS MORE THAN 600 MM ABOVE THE LEVEL ON THE OTHER SIDE OF THE ADJACENT SURFACE, OR
(b) THE ADJACENT SURFACE WITHIN 1.2 M FROM THE WALKING SURFACE HAS A SLOPE OF MORE THAN 1 IN 2.
(2) GUARDS ARE NOT REQUIRED,
(a) ON A RAMP,
(b) AT FLOOR PITS IN REPAIR GARAGES, OR
(c) ON THE SIDE OF A STAIR USED FOR MAINTENANCE PURPOSES ONLY.
(3) WHEN AN INTERIOR STAIR HAS MORE THAN 2 RISERS OR AN INTERIOR RAMP RISES MORE THAN 600 MM, THE SIDES OF THE STAIR OR RAMP THAT ARE NOT PROTECTED BY A WALL, FLOOR, OR THE STAIRWELL OR RAMP SHALL BE PROTECTED BY A GUARD ON EACH SIDE THAT IS NOT PROTECTED BY A WALL.

9.8.8.3 HEIGHT OF GUARDS
(3) EXCEPT AS PROVIDED IN SENTENCES (2) TO (4), ALL GUARDS SHALL BE NOT LESS THAN 1 070 MM HIGH.
(5) ALL GUARDS WITHIN DWELLING UNITS SHALL BE NOT LESS THAN 900 MM HIGH.
(6) EXCEPT AS PERMITTED IN SENTENCE (7), GUARDS SHALL BE NOT LESS THAN 1 070 MM HIGH WHERE THE WALKING SURFACE SERVED BY THE GUARD IS NOT MORE THAN 1 800 MM ABOVE THE FINISHED GROUND LEVEL.
(7) GUARDS SHALL BE NOT LESS THAN 900 MM HIGH WHERE THE WALKING SURFACE SERVED BY THE GUARD IS NOT MORE THAN 1 800 MM HIGH.
(8) THE HEIGHT OF GUARDS FOR FLIGHTS OF STEPS SHALL BE MEASURED VERTICALLY FROM A LINE DRAWN THROUGH THE LEADING EDGE OF THE TREADS SERVED BY THE GUARD.

9.8.8.7 GLASS IN GUARDS
(1) GLASS USED IN GUARDS SHALL BE,
(a) SAFETY GLASS OF THE LAMINATED OR TEMPERED TYPE CONFORMING TO CAN/CGSB-12.1-M, "TEMPERED OR LAMINATED SAFETY GLASS", OR
(b) WIRED GLASS CONFORMING TO CAN/CGSB-12.11-M, "WIRED SAFETY GLASS".

12.3.5.11. WINDOWS AND GLAZING
(1) EXCEPT AS PERMITTED IN SENTENCES (2) AND (3), WINDOWS AND ALL GLAZING THAT SEPARATES HEATED SPACE FROM UNHEATED SPACE OR THE EXTERIOR SHALL CONFORM TO ARTICLES 9.7.2.3.5. AND 12.3.5.8.
(2) EXCEPT AS PROVIDED IN SENTENCES (3) AND (4), THE TOTAL AREA OF GLAZING, INCLUDING GLAZING FOR DOORS AND DOOR LIGHTS, IN EACH ORIENTATION OF VERTICAL WALLS SHALL BE NOT MORE THAN THE VALUE GIVEN IN TABLE 12.3.5.11.-A FOR THE STOREY SERVED BY THE GLAZING AND WALLS WITH THAT ORIENTATION, EXPRESSED AS A PERCENT OF THE TOTAL AREA OF THE WALLS WITH THAT ORIENTATION, MEASURED ON THE BASIS OF THE OVERALL BUILDING DIMENSIONS AND THE FLOOR TO FLOOR HEIGHT OF THE STOREY SERVED BY THE GLAZING AND WALLS, INCLUDING ROOFED OVER SPACES, BUT EXCLUDING THE AREA OF THE PORTION OF THE WALL IS CALCULATED AS ITS PROJECTED AREA ON A VERTICAL PLANE.
(3) EXCEPT AS PROVIDED IN SENTENCE (4), THE TOTAL AREA OF GLAZING IN ANY ROOM SHALL BE NOT MORE THAN (1) AND ARTICLE 12.3.5.10., THE AREA OF SUCH GLAZING FOR THE PURPOSE OF APPLYING THIS SENTENCE (3) MAY BE MEASURED AS BEING EQUAL TO THE ACTUAL AREA MULTIPLIED BY THE RATIO OF THE REQUIRED THERMAL RESISTANCE DIVIDED BY THE ACTUAL THERMAL RESISTANCE OF THE GLAZING.
(4) THE TOTAL AREA OF GLAZING IN A ROOM MAY BE INCREASED BEYOND THE LIMIT PERMITTED IN SENTENCE (3) IF THE OVERALL THERMAL TRANSMITTANCE COEFFICIENT OF MORE THAN 5.0 % THAT IS UNSHADED IN THE WINTER AND FACES DUE SOUTH WITHIN 45° OF DUE SOUTH MAY BE ASSUMED TO BE 3 PERCENT OF ITS UNSHADED AREA IN CALCULATING THE MAXIMUM AREA OF GLAZING IN SENTENCE (3) (1) PROVIDED THE BUILDING IS DESIGNED TO BE COOLED UNLESS THE GLAZING DESCRIBED IN SENTENCE (4) IS SHADED IN THE SUMMER WITH EXTERIOR OVERHANGS FOR THE PURPOSE OF DETERMINING WHETHER OR NOT THE GLAZING IS SHADED IN THE SUMMER, SHADING SHALL BE CALCULATED USING THE NOON SUN ANGLES OF JUNE 21.

12.3.5.13. AIR INFILTRATION
(1) WINDOWS THAT SEPARATE HEATED SPACE FROM UNHEATED SPACE OR THE EXTERIOR SHALL BE DESIGNED TO LIMIT THE RATE OF AIR INFILTRATION TO NOT MORE THAN 0.775 L/S FOR EACH METRE OF SASH CRACK WHEN TESTED AT PRESSURE DIFFERENTIAL OF 75 PA IN CONFORMANCE WITH SENTENCE (2) OR AT A RATE OF NOT MORE THAN 1.5 L/S FOR EACH METRE OF DOOR CRACK THROUGH EXTERIOR WINDOWS, CURTAIN WALLS, AND DOORS UNDER SPECIFIED PRESSURE DIFFERENCES ACROSS THE SPECIMEN."
(2) MANUALLY OPERATED EXTERIOR SLIDING GLASS DOOR ASSEMBLIES THAT SEPARATE HEATED SPACE FROM UNHEATED SPACE OR THE EXTERIOR SHALL BE DESIGNED TO LIMIT THE RATE OF AIR INFILTRATION TO NOT MORE THAN 2.5 L/S FOR EACH SQUARE METRE OF DOOR AREA WHEN TESTED IN CONFORMANCE WITH SENTENCE (2).
(3) EXCEPT WHERE THE DOOR IS WEATHER-STRIPPED ON ALL EDGES AND PROTECTED WITH A STORM DOOR OR BY AN ENCLOSED VESTIBULE, EXTERIOR SWINGING DOOR ASSEMBLIES THAT SEPARATE HEATED SPACE FROM UNHEATED SPACE OR THE EXTERIOR SHALL BE DESIGNED TO LIMIT THE RATE OF AIR INFILTRATION TO NOT MORE THAN 5.0 L/S FOR EACH SQUARE METRE OF DOOR AREA WHEN TESTED IN CONFORMANCE WITH SENTENCE (2).
(4) DOOR ASSEMBLIES OTHER THAN THOSE DESCRIBED IN SENTENCES (2) AND (3), THAT SEPARATE HEATED SPACE FROM UNHEATED SPACE OR THE EXTERIOR SHALL BE DESIGNED TO LIMIT THE RATE OF AIR INFILTRATION TO NOT MORE THAN 7.0 L/S FOR EACH METRE OF DOOR CRACK WHEN TESTED IN CONFORMANCE WITH SENTENCE (2).
(5) CAULKING MATERIAL TO REDUCE AIR INFILTRATION SHALL CONFORM TO THE REQUIREMENTS IN SUBSECTION 9.27.4.
(6) EXCEPT AS PERMITTED IN SENTENCE (7), WHERE AN AIR BARRIER SYSTEM OR MATERIAL IS INSTALLED ON THE EXTERIOR (EITHER LOCATION-SPECIFIC OR THROUGHOUT) IT SHALL BE DESIGNED TO LIMIT AIR LEAKAGE INTO HEATED SPACES IN A BUILDING FROM THE EXTERIOR WALLS, SUCH AS AT UTILITY SERVICE ENTRANCES, SHALL BE CAULKED, GASKETED OR SEALED TO RESTRICT SUCH AIR LEAKAGE.
(7) WHERE AN AIR BARRIER SYSTEM OR MATERIAL IS INSTALLED ON THE EXTERIOR, THE PENETRATION OF SERVICES SHALL BE RESTRICTED IN CONFORMANCE WITH THE REQUIREMENTS OF SUBSECTION 9.25.3.

LEGEND

BWG — BIRD GAIN CONNECTION - REFER TO MECHANICAL DRAWINGS
NFHB — NON-FREEZE HOSE BIBB - REFER TO MECHANICAL DRAWINGS
WGR — WEATHERPROOF DUPLEX RECEPTACLE - REFER TO ELECTRICAL DRAWINGS
LF — LIGHT FIXTURE - REFER TO ELECTRICAL DRAWINGS
TG — TEMPERED GLASS

Typical Window Schedule Notes (3 / A4-15)
NTS

Window Schedule Legend (1 / A4-15)
NTS



Interior West Elevation - Part 5 (16 / A4-15)
Scale: 1 : 50



Interior West Elevation - Part 4 (15 / A4-15)
Scale: 1 : 50



Interior West Elevation - Part 3 (14 / A4-15)
Scale: 1 : 50



Interior West - Part 2 (13 / A4-15)
Scale: 1 : 50



Interior West Elevation - Part 1 (12 / A4-15)
Scale: 1 : 50



West Elevation - Part 22 (11 / A4-15)
Scale: 1 : 50



West Elevation - Part 21 (10 / A4-15)
Scale: 1 : 50

Contractor Must Check And Verify All Dimensions On The Job.
Do Not Scale The Drawings.
All Drawings, Specifications And Related Documents Are The Copyright Of The Architect And Must Be Returned Upon Request.
Reproduction Of Drawings, Specifications And Related Documents In Part Or Whole Is Forbidden Without The Architects Written Permission.
This Drawing Is Not To Be Used For Construction Until Signed By The Architect.

Date: November 4, 2016

ONTARIO ASSOCIATION OF ARCHITECTS
LICENCE
JOHN KIRKOR
"IT'S NOT AT SIGHT TO BE BLIND"
Construction

KIRKOR ARCHITECTS + PLANNERS
20 Martin Ross Avenue, Toronto, Ontario, M3J 2K8
Tel (416) 645-4045, Fax (416) 645-1234, www.kirkorarchitects.com

No.	Revision	Date
3.	Building Permit Resubmission	Nov. 1, 2017
2.	Construction	Nov. 4, 2016
1.	Tender	Oct. 13, 2015
No.	Issued For	Date

AQUAVISTA
AT BAYSIDE TORONTO

Drawing Title
Window Schedule - Level 2-4 - West, Interior West & Interior East Elevation

Project
Hines TRIDEL
AQUAVISTA
Block 3 - R3 & R4
263 Queens Quay East
Toronto, ON

Scale: As indicated
Drawn by: E.V. / M.N.
Checked by: C.A.
Project No.: 13148
Date: November 4, 2016
Drawing No.: A4-15

Plot Date: 11/1/2017 4:54:50 PM File Path: C:\Users\jtool\Documents\VEXT 2015 WORKING FILES\13148P20-Vestor-Building R3-R4_jtool.rvt