



MCW Consultants Ltd.

Addendum

Date: Jan. 06, 2016

Queen's Quay Terminal
207 Queen's Quay West, Suite 615
Toronto, Ontario M5J 1A7

Phone (416) 598-2920
Fax (416) 598-5394
www.mcw.com

Project Name: AQUAVISTA - Bayside
Client: TRIDEL Corporation
To: TRIDEL Corporation
Attention: Chadi Loza
Fax number: -

Project No.: 8489D
ADD No.: E 002
Page No.: 1 of 3+ Attached
Office: Toronto
From: Sunanda Perera
Tao Li

Distribution: Vince Mirarchi –TRIDEL
Solvera Gomes TRIDEL
Christina Lee -KIRKOR
Al Medeiros –MCW
Michael Hunter-MCW
Mark Furtado-MCW
Sarfraz H. Jaffrey-MCW

In accordance with the drawings and specifications, provide in the tender all costs required to complete the work including items as listed below:

Title: Various Electrical Changes.

Specification:

Spec	Issued	Items
<u>Panel (Condo)</u> 'P-2P1RCAP' 'P-2P1RCAM' 'P-2P1RCPE' 'P-2E1RCPT' 'P-6EP1RCP1' <u>Panel (Artscape)</u> 'P-2P1MRAP' 'P-2RRAP' 'P-2RRAM' <u>Panel (Retail)</u> 'P-61MCRP' 'P-2E1MCRP1'	Yes	- Panel schedule has been revised. Changes are highlighted as shown - Panel 'P-2P1RCAP' change to 84 CCT. - Panel 'P-2P1RCAM' change to 60 CCT.
Panel (Condo) 'P-22RCAP'	Yes	Add new panel.

Electrical:

Drawing No.	Drawing Issued	Items
E1-02	Yes	- Add fire alarm pull stations and exit signs on door Grid p2/Pg and Grid p16/Ph on P2 level as shown. - Revise exit signs type on P2 level as shown.

		- Revise electrical car changing stations circuit number as shown. - Revise lighting fixtures and control devices circuit number on P1 level as shown. - Add type 'P2' fixture (qty-2) on P1 level as shown.
E1-03	Yes	- Delete door opener in women's B.F. Shower as shown. - Add panic alarm in Mens and Womens change room as shown. - Add hand dryers in washrooms and change rooms as shown. - Add power connections for auto faucet in washroom as shown.
E2-01A	Yes	- Delete intercom station at West & East Entrance Vestibule as shown. - Add hand dryers and power connections for auto faucet in washroom in west main lobby as shown. - Add lighting fixtures at U/S of stair stringer as shown. - Add one 21mmC conduit to security room in East Entrance Vestibule as shown. - Delete the normal temporary lighting fixtures in retail area as shown. - Add emergency call system conduit rough-ins in Universal W.C. as shown.
E2-01B	Yes	Delete the normal temporary lighting fixtures in retail area as shown.
E2-02A	Yes	Add hand dryer and power connection for auto faucet in B.F. W.C. in Artscape reception as shown.
E2-03A	Yes	- Add circuit numbers and control devices for lighting fixtures in amenity area as shown. - Add general receptacles in amenity area as shown. - Add hand dryers and power connections for auto faucet in amenity area washrooms as shown. - Add emergency call system conduit rough-ins in Universal W/C & Change Room as shown.
E2-03B	Yes	Provide door opener on door in pool area as shown.
E2-14A	Yes	Revise circuit number for battery units in Generator Rooms as shown.
E2-14B	Yes	- Add hand dryer and power connection for auto faucet in Universal W/C as shown. - Add emergency call system conduit rough-ins in Universal W/C as shown.
E3-01	Yes	- Single line diagram has been revised to match with metering requirement. - Add panel 'P-22RCAP' as shown. - Transformer 'TX-RCE3' shall be fed from the main section of the switchboard by adding a separate overload protection as shown. - Revise breaker size for fire pump as shown.



MCW Consultants Ltd.

Project Name: Aquavista
To: TRIDEL Corporation

Project No.: 8489D
ADD No.: E 002
Page No.: 3 of 3

E3-02	Yes	• Rearrange breakers in panel 'DP-6ERRA' as shown. • Add splitter 'SP-2P1MRA-EV' for electrical car charging stations, and add 50A/3P breaker in panel 'DP-2RA' as shown.
E5-01	Yes	• Add splitter 'SP-2P1MRA-EV' for electrical car charging stations as shown. • Rearrange panel location as shown.

ME SCHEDULE:

Drawing No.	Drawing Issued	Items
ME-12	Yes	• Revise fire pump and jokey pump size per sprinkler consultants drawing.

Reason for Issue-Design complete.

End of ADD E-002