



LEGEND : WALL SCONCE & PENDANT MOUNTING HEIGHTS	
NOTE: ALL PENDANT DIMENSIONS ARE FROM UNDERSIDE OF FIXTURE TO FINISHED FLOOR. ALL WALL SCONCE DIMENSIONS ARE FROM CENTRE OF FIXTURE TO FINISHED FLOOR	
FIXTURE	MOUNTING HEIGHT
L22A	2575MM
L22B	1440MM

1. MECHANICAL AND ELECTRICAL WORK TO COMPLY WITH THE REQUIREMENTS OF THE BUILDING REGULATIONS AND AUTHORITIES HAVING JURISDICTION.
2. PROVIDE TO DESIGNER DRAWINGS OF LOCATION OF CEILING FIXTURES REFER TO ENGINEERING DRAWINGS FOR SPECIFICATIONS.
3. CONTRACTOR TO CROSS REFERENCE BETWEEN DESIGNER'S ELECTRICAL DRAWINGS, ENGINEER'S MECHANICAL DRAWINGS AND SITE CONDITIONS. REPORT DISCREPANCIES TO DESIGNER FOR CLARIFICATION.
4. CONTRACTOR TO PROVIDE DRAWINGS IN SPYRAL BOUND TO ACCOMMODATE SPRINKLER, EXIT LIGHTS, ACCESS PANELS, RECESSED DOWN LIGHTS AND DIFFUSERS. PROVIDE TO DESIGNER REFER TO SPECIFICATIONS FOR SPECIFICATIONS OF DRAWINGS AND SPECIFICATIONS.
5. ALL FIXTURES AND SWITCHES TO BE LOCATED IN ACCORDANCE WITH DESIGNER'S REPORT DISCREPANCIES TO THE DESIGNER PRIOR TO INSTALLATION.
6. CONTRACTOR TO PROVIDER AIR TRANSFER DUCTS IN ACCORDANCE WITH MECHANICAL DRAWINGS WHERE CONSTRUCTION OCCURS ABOVE SUSPENDED CEILING TO 1/2" OF SLAB.
7. REFER TO ENGINEERING DRAWINGS FOR LIFE SAFETY SYSTEMS.
8. ELECTRICAL CONCEPT TO CONFIRM QUANTITY AND LOCATION OF LUMINAIRES. REQUIRED TO ACHIEVE LIGHTING LEVELS AND DISTRIBUTION AS REQUIRED BY LOCAL REGULATORY CODES AND REGULATIONS.
9. ALL LIGHT FIXTURE TO BE ON OWNERS.
10. CONTRACTOR TO CONFIRM CEILING HEIGHT & CONDITIONS AND NOTIFY DESIGNER OF ANY DISCREPANCIES.
11. OBTAINMENT IN LEADING SUPPLIER TO VERIFY QUANTITY OF FIXTURES PRIOR TO ORDERING AND INSTALLING.

5. DRAWINGS NOT TO BE SCALED	
Issue:	
01 ISSUED FOR COORDINATION	15.04.09
02 ISSUED FOR COORDINATION	15.04.13
04 ISSUED FOR COORDINATION	15.11.11
05 ISSUED FOR COORDINATION	16.01.11
06 ISSUED FOR CLIENT REVIEW	16.01.15
07 ISSUED FOR TENDER	16.03.18
08 ISSUED FOR ADDENDUM	16.09.20
09 ISSUED FOR ADDENDUM	17.01.27
10 ISSUED FOR CONSTRUCTION	17.06.19

01 ISSUED FOR COORDINATION	15.04.09
02 ISSUED FOR COORDINATION	15.04.13
04 ISSUED FOR COORDINATION	15.11.11
05 ISSUED FOR COORDINATION	16.01.11
06 ISSUED FOR CLIENT REVIEW	16.01.15
07 ISSUED FOR TENDER	16.03.18
08 ISSUED FOR ADDENDUM	16.09.20
09 ISSUED FOR ADDENDUM	17.01.27
10 ISSUED FOR CONSTRUCTION	17.06.19
-	-
-	-
-	-
-	-

ID3.18